Stanford House High Street Oxford



Archaeological Watching Brief Report



May 2014

Client: BGS Architects

Issue No: 1 OA Job No: 5893 NGR: SP 519062



Client Name: BGS Architects

Client Ref No:

Document Title: Stanford House, High Street, Oxford

Document Type: Archaeological Watching Brief Report

Issue/Version Number: 1

Grid Reference: SP 519062

Planning Reference: 13/03351/FUL

Invoice Code: OXSTANWB

OA Job Number: 5893

Site Code: OXSTAN 14

Receiving Museum: Oxfordshire County Museums Services

Museum Accession No.: OXCMS:2014.85

Event No.:

Issue	Prepared by	Checked by	Approved by	Signature
1	Brian Dean Project Officer	Dan Poore	Dan Poore Head of Fieldwork	Doos

Document File Location: X:\s\Stanford House, Oxford

Graphics File Location:

Illustrated by:

Disclaimer:

This document has been prepared for the titled project or named part thereof and should not be relied upon or used for any other project without an independent check being carried out as to its suitability and prior written authority of Oxford Archaeology being obtained. Oxford Archaeology accepts no responsibility or liability for the consequences of this document being used for a purpose other than the purposes for which it was commissioned. Any person/party using or relying on the document for such other purposes agrees, and will by such use or reliance be taken to confirm their agreement to indemnify Oxford Archaeology for all loss or damage resulting therefrom. Oxford Archaeology accepts no responsibility or liability for this document to any party other than the person/party by whom it was commissioned.

© Oxford Archaeology Ltd 2014

Janus House

Osney Mead Oxford OX2 0ES

t: +44 (0) 1865 263800 e: info@oxfordarch.co.uk f: +44 (0) 1865 793496 w: oxfordarchaeology.com

Oxford Archaeology Limited is a Registered Charity No: 285627



Stanford House, High Street, Oxford Archaeological Watching Brief Report

Written by Brian Dean

and illustrated by Hannah Kennedy

Table of Contents

S	ummary	. 2
1	Location and Scope of Work	. 2
2	Methodology	. 2
3	Description of Deposits	. 2
4	Discussion and Conclusions	3



Summary

Oxford Archaeology were commissioned by BGS Architects, on behalf of Stanford University, to carry out an archaeological watching brief on a geotechnical trial trench in advance of the erection of a garden building at Stanford House, High Street, Oxford. The work was carried out as a condition of planning permission (planning ref 13/03351/FUL) in accordance with a methodology agreed with David Radford, Archaeologist for Oxford City Council. Late 19th-century and modern services were revealed; no deposits pre-dating this period were observed during the watching brief.

1 LOCATION AND SCOPE OF WORK

- 1.1.1 The site is centred on SP 519 062. The area for the proposed development is within a garden to the rear of Stanford house, 65 High Street, Oxford (Fig.1).
- 1.1.2 The geology of the area is superficial Northmoor Sand and Gravel overlying Oxford Clay (BGS).
- 1.1.3 The proposed works will involve the erection of a new garden building and covered link using a ground slab. Foundation details are yet to be decided. The ground slopes down slightly towards the south. The garden building is *c* 4.2m x 20.6m and the covered link is *c* 8.5m x 2.2m. Geotechnical investigation was required to confirm the strength of the made ground, and allow the finalisation of the design of the ground bearing (raft) structural solution.
- 1.1.4 The geotechnical investigation required the excavation of a trial trench running along the line of the west and south walls of the proposed building (see Fig. 1).

2 METHODOLOGY

- 2.1.1 The geotechnical trench was hand dug by the groundworks contractor to avoid unnecessary damage to nearby trees. The trench measured 500mm wide and was no deeper than 800mm. It was during this work that the archaeological observations took place, on the 27th, 28th and 31st March 2014.
- 2.1.2 The majority of the excavation with the potential to disturb archaeological deposits or features was closely monitored and time was allowed by the contractor for the archaeological project supervisor to examine the trench and the deposits therein. The east-west trench, corresponding to the south wall of the proposed building, was not monitored as it was felt that sufficient information had been gathered during the monitoring of the north-south trench line.

3 Description of Deposits

- 3.1.1 The northern end of the trench comprised a topsoil layer overlying made ground. This overlay an east-west oriented brick encased service run of approximately 1m in width that serviced the nearby conservatory building. This was predicted to continue across the garden to the west. This truncated an earlier drain oriented north-south which roughly followed the alignment of the trial trench.
- 3.1.2 A further east-west oriented drain was observed towards the centre of the trench which fed into a manhole and also truncated the north-south drain.



3.1.3 The southern half of the trench comprised a topsoil overlying a layer of building rubble containing frogged bricks, mortar and occasional fragments of concrete and plastic. Underlying the rubble layer was a deposit of mid grey sandy-silt that also contained bricks.

4 DISCUSSION AND CONCLUSIONS

- 4.1.1 The trial trench revealed no features or deposits dating to before the late 19th century. The deposits observed illustrate a sequence of services associated with the extant structures, with earlier drainage runs being truncated by them. In addition, rubble was observed below the topsoil which may indicate either a pre-existing structure or a dump of building material associated with the construction of the current structures on the site.
- 4.1.2 It therefore seems likely that any significant archaeological horizons at the site lie at depths in excess of 800mm.






Figure 2: Plan of site and features



Head Office/Registered Office/ OA South

Janus House Osney Mead Oxford OX20ES

t: +44(0)1865 263800 f: +44(0)1865 793496

e:info@oxfordarchaeology.com w:http://oxfordarchaeology.com

OA North

Mill3 MoorLane LancasterLA11QD

t:+44(0)1524 541000 f:+44(0)1524 848606 e:oanorth@oxfordarchaeology.com w:http://oxfordarchaeology.com

OA East

15 Trafalgar Way Bar Hill Cambridgeshire CB23 8SQ

t:+44(0)1223 850500 e:oaeast@oxfordarchaeology.com w:http://oxfordarchaeology.com



Director: GIII Hey, BA PhD FSA MIFA Oxford Archaeology Ltd is a Private Limited Company, N^O: 1618597 and a Registered Charity, N^O: 285627